N

NOTES

THIS SURVEY IS ORIENTATED TO ORDNANCE SURVEY GRID NORTH. THE SURVEY IS TO A PLANE GRID. HORIZONTAL MEASUREMENTS TAKEN FROM THIS SURVEY WILL BE GROUND DISTANCES.

ALL LEVELS RELATE TO ORDNANCE SURVEY DATUM GENERATED BY ACTIVE GPS NETWORK.

LEGEND

- 30.29 SPOT LEVEL
- SURVEY STATION
- SAPLING
- BUSHES/SHRUB
- TREE (INDICATIVE ONLY)
- HEDGE/AREA OF UNDERGROWTH
- 99.99 CONTOUR
- GATE
- OVERHEAD CABLE
- FENCE

ABBREVIATIONS

Ar/L	ARCH LEVEL	LB	LETTER BOX
AV	AIR VALVE	LP	LAMPOST
B	BOLLARD	MH	MANHOLE
BB	BELISHA BEACON	MKR	MARKER
BH	BOREHOLE	OHC	OVERHEAD CABLE
BL	BED LEVEL	OpL	OPENING LEVEL
BS	BUS STOP	OSBM	OS BENCHMARK
BT	BT COVER	P	POST
C/B	CLOSED BOARD FENCE	P/R	POST AND RAIL FENCE
C/L	CHAIN LINK FENCE	P/W	POST AND WIRE FENCE
CATV	CABLE TELEVISION COVER	PEC	PEDESTRIAN CROSSING
CC	CONTROL CABIN	PM	PARKING METER
COL	COLUMN	RE	RODDING EYE
Concp	CONCRETE PANEL FENCE	RWL	RETAINING WALL
CPY	CANOPY	SAP	SAPLING
C/L	CROWN LEVEL	SEC	SECURITY CAMERA
Ctly	CABLE STAY	SGY	STRIP GULLY
CTV	CABLE TELEVISION POINT	SoL	SOFFIT LEVEL
CYR	CYCLE RACK	SP	SIGNPOST
DK	DROPPED KERB	SpL	SPRINGING LEVEL
DP	DOWNPIPE	SV	STOP VALVE
EIP	ELECTRIC INLET POINT	T/Pit	TRIAL PIT
EL	ELECTRIC INSPECTION COVER	TCB	TELEPHONE BOX
EP	ELECTRICITY SUPPLY POLE	TE/?	TREE + NUMBER
ER	EARTH ROD	THL	THRESHOLD LEVEL
FH	FIRE HYDRANT	TL	TRAFFIC LIGHT
G	GULLY	ToF	TOP OF FENCE
G/DP	GULLY AND DOWNPIPE	ToW	TOP OF WALL
GP	GATE POST	TP	TELEPHONE POLE
Gpi	GAS PIPE	W/M	WIRE MESH FENCE
GV	GAS VALVE	W/P	WOODEN PANEL FENCE
IC	INSPECTION CHAMBER	WLV	WATER LEVEL
IL	INVERT LEVEL	WM	WATER METER
I/R	IRON RAILING FENCE	WO	WASH OUT
KO	KERB OUTLET		

STATION CO-ORDINATES

STATION	EASTING	NORTHING	LEVEL	DESCRIPTION
STN/1	636514.87	149394.51	49.75	Survey Nail
STN/2	636544.62	149493.82	48.08	Survey Nail
STN/50	636689.30	149787.44	36.83	Survey Nail
STN/51	636631.90	149676.97	40.28	Survey Nail
STN/53	636584.22	149582.65	43.27	Survey Nail

TREE SCHEDULE

No.	DIAM.	SPREAD Ø	HEIGHT
TE/1	0.30	8	8
TE/2	0.20	4	4
TE/3	0.20	4	4
TE/4	0.40	4	4
TE/5	0.30	4	4
TE/6	0.30	4	4
TE/7	0.30	4	4
TE/8	0.60	6	4
TE/9	0.40	6	4
TE/10	0.40	6	4
TE/11	0.40	6	4
TE/12	0.60	6	4
TE/13	0.40	6	4
TE/14	0.40	6	4
TE/15	0.20	6	4
TE/16	0.60	6	4
TE/17	0.60	6	4
TE/18	0.60	6	4
TE/19	0.60	6	4
TE/20	0.60	6	4
TE/21	0.30	6	4
TE/22	0.30	6	4
TE/23	0.60	6	4
TE/24	0.30	6	4
TE/25	0.30	6	4
TE/26	0.30	6	4
TE/27	0.60	6	4
TE/28	0.60	6	4
TE/29	0.60	6	4
TE/30	0.60	6	4
TE/31	0.20	6	4
TE/32	0.60	6	4
TE/33	0.20	6	4
TE/34	0.60	6	4
TE/35	NUMBER	NOT	USED
TE/36	0.60	6	4
TE/37	0.60	6	4
TE/38	0.60	6	4
TE/39	0.40	6	4
TE/40	0.40	6	4
TE/41	0.40	6	4
TE/42	0.40	4	6
TE/43	0.40	8	8
TE/44	0.30	8	8
TE/45	0.20	4	4
TE/46	0.20	6	6
TE/47	0.30	6	6
TE/48	0.30	6	6
TE/49	0.40	6	6
TE/50	0.60	6	6
TE/51	0.50	10	8
TE/52	0.25	6	6
TE/53	0.20	5	10
TE/54	0.85	12	12
TE/55	0.20	4	10
TE/56	0.70	12	16
TE/57	0.25	6	10
TE/58	0.50	14	16
TE/59	0.30	5	8
TE/60	0.15	5	8
TE/61	0.15	5	8
TE/62	0.25	6	8
TE/63	0.70	8	10
TE/64	0.20	6	8
TE/65	0.20	6	8
TE/66	0.40	8	8
TE/67	0.30	8	8
TE/68	0.50	8	10
TE/69	0.20	8	8
TE/70	0.20	8	8
TE/71	0.70	10	10
TE/72	0.40	6	8
TE/73	0.40	8	12
TE/74	0.30	8	12
TE/75	0.40	8	12
TE/76	0.20	8	12
TE/77	0.20	8	12
TE/78	0.35	8	12
TE/79	0.15	8	12
TE/80	0.15	8	12
TE/81	0.15	8	12
TE/82	0.40	8	12
TE/83	0.20	8	12
TE/84	0.40	14	11
TE/85	0.35	14	16
TE/86	0.50	14	8
TE/87	0.90	20	14
TE/88	0.60	8	8
TE/89	0.70	14	15
TE/90	0.20	4	5

TREE DIAMETER MEASURED APPROXIMATELY 1.5M ABOVE GROUND LEVEL. TREE SPREADS ARE SYMBOLIC ONLY AND ARE REPRESENTATIVE OF THE GENERALISED CANOPY SIZE. TREE BOLE MAY NOT SIT CENTRALLY TO THE CANOPY. TREE HEIGHT ESTIMATED FROM GROUND LEVEL.

Rev	Date	Revision notes	By
*	*	*	*

DO NOT SCALE

Status

INFORMATION

Project

DOVER ROAD, DEAL

Title

TOPOGRAPHICAL SURVEY AS OF 12.01.17 SHEET 1 OF 1

GLADMAN
Gladman House, Alexandria Way
Congleton Business Park
Congleton, Cheshire
CW12 1LB
Tel: 01260 288800
Fax: 01260 288801
www.gladman.co.uk

Drawn By	Publish Date	Scale(s)	Sheet Size
JW/JH	17.01.17	1:500	A0

Project no.	Drawing no.	Revision
2016-124	Topo_01_2D	0