



TYPICAL MINIMUM SPECIFICATION
FOR GC6 HOUSING - CLIENT MAY
PROPOSE ALTERNATIVES IF
NECESSARY

- FLOOR SLAB
1. CONCRETE SHALL BE GRADE C30.
 2. VERTICAL FACES SHALL BE FORMED USING FULL DEPTH PLYWOOD SHUTTERING.
 3. TOP SURFACE SHALL BE FLAT AND EVEN, FINISHED WITH A STEEL TROWEL TO GIVE A SMOOTH, TIGHT SURFACE.
 4. ALL SHUTTERING SHALL BE REMOVED PRIOR TO INLET OR OUTLET PIPEWORK INSTALLATION.
 5. THE GAP BY THE INLET AND OUTLET SHALL BE FILLED WITH C30 GRADE CONCRETE AFTER PIPE INSTALLATION, BUT BEFORE METER INSTALLATION.

SUITABLE FOR U65

APPROVED FOR
CONSTRUCTION

2	Approved for construction	03/03/2020	PA	DS
1	Text added	18/02/2020	PA	DS
0	Original Issue	16/09/2019	PA	DS
Rev	Amendment	Date	Drwn	Chkd

HIGHVOLTAGE
SYSTEMS&SERVICES

High Voltage System & Services Ltd.
Forest House
2 Riley Road
Telford Way Industrial Estate
Kettering NN16 8NN
TELEPHONE: 01604 781 107

Drawing Title GC5 METER ENCLOSURE (LP)	
Scale 1/15	Orig. Page Size A3
Drawing No. LD204	Sheet 1/1